



information bulletin

toll free 1800 246 199 ▪ www.roadreport.nt.gov.au

Road Closures

Arnhem and Kakadu Highways

General

Currently the **Arnhem Highway** has road closures in place as follows:

- Arnhem Highway between the Window to Wetland and the eastern end of the Adelaide River floodplain and between Point Stuart Road and Kapalga Community Access;
- The section across the Adelaide River floodplain is expected to be open to **4X4** by mid week.

The **Arnhem Highway** will be undergoing repair and patching in the newly opened sections and travellers will need to heed warning signs and directions.

The **Kakadu Highway** has been reopened with weight and vehicle type restrictions in place as follows:

- Kakadu Highway between Gimbat Road intersection and the Arnhem Highway intersection – 100% axle group limits, maximum 13 axles, empty travel permitted.

Motorists are advised of road damage at Nourlangie Creeks and Jim Jim River where caution is required and speed restrictions are in place. Temporary repairs are being carried out at these locations.

You are referred to the Department's road reporting **website** above for more detail of these restrictions.

Arnhem Highway – Bridging of the West Alligator West Branch River Crossing

A new bridge consisting of a single 15m span is being constructed on the Arnhem Highway at 150.6 km from the Stuart Highway It will replace the reinforced concrete box culvert damaged during runoff from Tropical Low George and will cost around one million dollars.

Construction work commenced on 11 March and piling has now been completed. They will support concrete abutments at either end which in turn support precast concrete deck units.

1/2

2/2

The manufacture of the precast units has commenced and will continue whilst concrete abutment works are proceeding.

It is envisaged that the bridge will be able to be trafficked by late March and take a further 1 – 2 weeks to be fully complete.

Regular updates will be provided on the progress of the Department with its investigations and works to construct a bridge over the damaged culvert.

Issued at 13:30 hrs. 13/3/07